Resurface Project Record

Project Name:	**Notnomis Rd**							
Description:	Hwy 27 To Spradlin Rd.							
Length(Mi):	1.3							
Material	Length	Width	Sq. Yd.	#'s/ SqYd		Tons		
Leveling	6864	20	15253.33	45		343.20		
Topping	6864	20	15253.33	165		1258.40		
Tack	6864	20	15253.33	0.1		1525	(Gal)	
Solid Traffic 5" White	2.6							
Solid Traffic 5"Yellow	1.17							
Skip Traffic 5"Yellow	0.13							